



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: Box #18107, Wichita, Kansas.

Lease Name: Pinkston Well No. A-1

Location: NW-SW-NE Sec. 4 Twp. 18 Rge. (E)(W) 29

County: Lane Total Depth 4600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

453'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 350'.

Circulate hole with heavy mud. Pull DP to 600' and displace 90 Sx.
cement thru DP. Pull DP, set plug @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx.
cement to bottom of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent