

To: 1120992 12-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,381-0000
C SW NW, SEC. 36, T 18 S, R 29 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Hilgenberg Well # 1

Operator: A.L. Abercrombie, Inc.

County Lane

Name & Address Rt. 1, Box 56

Well Total Depth 4650 151.13 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:30 a.m. Day: 2 Month: 12 Year: 1994

Plugging proposal received from Joe Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4372' w/200 sx cement, PBTD 4333', Perfs at 4206-09, 4220-23, 4242-45'

1st plug sand back to 4150' and dump 4 sx cement on top of sand through bailer,

2nd plug at 2160' with 50 sx cement, 3rd plug at 1300' with 80 sx cement,

4th plug at 600' with 40 sx cement, 5th plug at 280' with 40 sx cement,

6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Macey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:45 p.m. Day: 2 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4150' and dumped 4 sx cement on top of sand through bailer,

2nd plug ripped 4 1/2" casing at 1300', casing not free, pumped 80 sx plug and displaced to 850'. Shut in at 800#.

3rd plug ripped 4 1/2" casing at 800'. Layed down 200' of 4 1/2" casing and spotted 40 sx cement at 600'. 4th plug pulled casing to 300' and spotted 40 sx cement. 5th plug pulled casing to 40' and circulated cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(If XXXXXX observe this plugging.)

INVOICED

Signed Duan Parker (TECHNICIAN)

DATE 12-12-94

INV. NO. 41884

