

To: 1090507  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,457-0000  
SW NE NW, SEC. 36, T 18 S, R 29 W/E  
4290 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Hilgenberg Well # 2

Operator: A.L. Abercrombie, Inc.

County Lane

Name & Address Rt. 1, Box 56

Well Total Depth 4650 151.13 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 12 Year: 1994

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4436' w/200 sx cement, CIBP 4238', Perfs at 4185-88, 4224-27, 4249-50, 4311-17'

1st plug sand back to 4130' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 80 sx cement at 1300', 3rd plug pump 40 sx cement at 600',

4th plug pump 40 sx cement at 300', 5th plug pump 40 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 4 sx cement on top of sand through bailer,

2nd plug shot casing at 1300' and pumped in 80 sx cement,

3rd plug shot casing at 680' and pumped in 40 sx cement,

4th plug pulled to 330' and circulated 100 sx cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 680' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  observe this plugging.

DATE 12-12-94

INV. NO. 41886

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
12-6-94  
DEC 06 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS