

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,896-0000SW, Sec. 5, T 18 S, R 29 W1990 feet from X/S section line1990 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181Lease Name HAHN 'E' Well # 1

Operator: DONALD C. SLAWSON
Name & Address 200 Douglas Building
WICHITA, KS 67202

County LANEWell Total Depth 4615 feet 149.99Conductor Pipe: Size 8 5/8 feet 389Surface Casing: Size 8 5/8 feet 389Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor SLAWSON DRILLING Co, Inc License Number 5657Address 200 Douglas Bldg, WICHITA, KS 67202Company to plug at: Hour: 9:30A Day: 23 Month: DEC Year: 1983VERBAL PLUGGING ORDERS GIVEN TO TOM BARNES(company name) SLAWSON (phone)

were to use 60/40 Pozmix w/2% gel - 3% CC and spot the
1st plug @ 2130' w/50 dy - 2nd plug @ 1650 w/50 dy
3rd plug @ 1080 w/50 dy - 4th plug @ 450 w/40 dy
5th plug @ 40' w/solid bridge, plug and 10 dy.
Circulate 15 dy in the rat hole.

Signed R. B. Starbuck
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 7:45P Day: 23 Month: DEC Year: 1983ACTUAL PLUGGING REPORT plugged as ordered.

Cementing by Halliburton.
Cement ticket # 606202

Remarks:

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~was~~ / did not) observe this plugging.

INVOICED

DATE 1-13-84INV. NO. 9046 W

12-30-83

Signed R. B. Starbuck
(TECHNICIAN)