

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20, 767-6000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Name & Address  
Mull Drilling Company  
P.O. Box 2758  
Wichita, Kansas 67201

5/2 SWSE, Sec. 7, T 18 S, R 29 W/E  
330 feet from N/S section line

1980 feet from W/E section line

Lease Name Waterson Trust Well #1 "A" R

County Lane

Well Total Depth 4635 feet 150.64 R

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Martin Drilling Company license Number 6037 rig/613

Address 617 Union Center Wichita, KS 67202

Company to plug at: Hour: 10:00am Day: 24 Month: March Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bill Rider

(company name) Martin Drilling Company (phone) \_\_\_\_\_

were: 50/50 Pozmix 4% gel 3% cc

1st Plug @ 2190' w/50sx, 2nd Plug @ 1090

w/50sx, 3rd Plug @ 790' w/40sx, 4th Plug @

40' w/solid Bridge Plug + 10sx Circulate 15sx

in rathole + Circulate 10sx in Mousehole

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:00am Day: 24 Month: March Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Anhydrite 2156 2210

Haliburton did the cement work

Remarks: Mr Robert Tarbutton did give plugging orders

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 4-14-83

INV. NO. 3984-W

RECEIVED  
STATE CORPORATION COMMISSION  
3-29-83  
MAR 29 1983

Signed Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82