

1 060754

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,259-0000

SE SW SW, SEC. 8, T 18 S, R 29 W2E
340 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Ehmke Well # 1

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

County Lane 151.13
Well Total Depth 4650 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 31 Month: December Year: 19 85

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2828'
Anhydrite 2200'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 12:30 am Day: 1 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1330' with 80
sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE JAN 13 1986

INV. NO.

11940

Signed

Paul A. Luthi / rjl
(TECHNICIAN)

1-6-86