

To: 1 051596 11-6  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,638 -0000 29R  
NW SW SE, SEC. 17, T 18 S, R 29 W/E  
990 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860  
Operator: Castle Resources, Inc.  
Name & Address: 1200 E. 27th St., Ste.C  
Hays, KS 67601

Lease Name Schwartz Well # 1  
County Lane  
Well Total Depth 4590 149.18 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241  
Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 3:30 a.m. Day: 6 Month: 11 Year: 19 92

Plugging proposal received from Rick Finnesy  
(company name) Emphasis Oil Operations (phone) 913-483-3518

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2175-2202'  
1st plug at 2200' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 40 sx cement, 4th plug at 250' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:45 a.m. Day: 6 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,  
2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 40 sx cement,  
4th plug at 250' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

NOV 11-72-92  
12-1992  
KANSAS CORPORATION COMMISSION

INVOICED

(if additional description is necessary, use BACK of this form.)

DATE 11-24-92  
I CERTIFY / did not observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 36916