

1040151

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,985-~~0000~~
Approx. C SE SW, SEC. 18, T 18 S, R 29 W/E

350 feet from X/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Reifschneider Well # 1

Operator: John Jay Darrah, Jr.

County _____ Lane _____

Name & Address 405 Century Plaza

Well Total Depth 4650 151.13 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Mallard Drilling Co., Inc. License Number 5651

Address 405 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 9:30 am Day: 7 Month: July Year: 19 84

Plugging proposal received from Jay Schneider

(company name) Mallard (phone) 316-525-6934

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1085' with 60 sx cement

3rd plug at 300' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Edgar M. Knobloch
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00 pm Day: 7 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1085' with 60

sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1984

7-11-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACK of this form)

INVOICED

DATE 7-16-84

INV. NO. 2539

7-7

Signed Edgar M. Knobloch
(TECHNICIAN)