

1 070208

134 R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,507-K0001

NE SE, SEC. 4, T 18 S, R 29 W/R
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050Lease Name Pinkston Well # 4-9

Operator: Alfa Resources, Inc.
Name &
Address 511 16th St., Suite 300
Denver, CO 80212

County Lane 171.50Well Total Depth 5277 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 227Abandoned Oil Well x Gas Well Input Well SWD Well D&A Other well as hereinafter indicated Plugging Contractor Kelso Casing Pulling License Number 6050Address P.O. Box 347 Chase, KS 67524Company to plug at: Hour: 2:40 p.m. Day: 20 Month: 8 Year: 1986Plugging proposal received from Vernon Duntz(company name) Kelso (phone) 316-938-2457were: 4 1/2" at 4607' PBTD 4607' Perfs at 4213-19', 4553-57'1st plug sand back to 4170' and dump 4 sx cement

2nd plug squeezed well with 3 sx hulls, 15 gel, 50 sx cement, 10 sx gel, 1 sx hull,
release 1 plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None Operations Completed: Hour: 3:30 p.m. Day: 20 Month: 8 Year: 1986ACTUAL PLUGGING REPORT 1st plug sand to 4170' and dumped 4 sx cement

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
released plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Recovered 1900' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICE Observe this plugging.DATE 8-26-86INV. NO. 14816

Rec'd
8-25-86
AUG 25 1986

Signed Dan Goodrow
(TECHNICIAN)