

To: 1 040273
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-14
API NUMBER 15-101-21.511-0000

NE NW NE, SEC. 1, T 18 S, R 29 W/E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420 & 7245

Lease Name Hallibick Well # 1-1

Operator: White & Ellis Drilling, Inc.
Name & Address & Texas-El Dorado Oil Company
401 East Douglas, Suite 500
Wichita, KS 67202

County Lane Lane 148.20

Well Total Depth 4560 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 14 Month: 5 Year: 19 89

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2128-60'
1st plug at 2160' with 50 sx cement, 2nd plug at 1380' with 80 sx cement,
3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

 Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9 a.m. Day: 14 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1380' with 80 sx cement,
3rd plug at 280' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1989
5-16-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED to serve this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 5-17-89

INV. NO. 24883