

1 070785

1-31

Handwritten initials

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,520-0000

SW NE SE, SEC. 1, T 18 S, R 29 W/E
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Peck Well # 1-1

Operator: Landmark Oil Exploration, Inc.
Name &
Address 250 North Water, Suite 308
Wichita, KS 67202

County Lane 14.69
Well Total Depth 4575 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Landmark Oil Exploration, Inc. License Number 6113

Address 250 North Water, Suite 308, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 31 Month: 1 Year: 19 90

Plugging proposal received from Russell Bright

(company name) Landmark Oil Exploration, Inc. (phone) 316-265-8181

were: 4 1/2" at 4573' Perfs at 4303-06, 4228' Elevation 2744' GL

1st plug sand back to 4170' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 75 sx cement, 10 sx gel, 1 sx hulls, and 150 sx
cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 31 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4170' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls,
and 150 sx cement down 8 5/8".

Maximum pressure 1600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

FFB
2-7-90

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 2-12-90

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 27416