

To: 1 120993 12-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

101-20611-0000
API NUMBER 15- ~~Docket #D-20,690-0000~~
SW NW NW, SEC. 36, T 18 S, R 29 W/E
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address Rt. 1, Box 56
Great Bend, KS 67530

Lease Name Hilgenberg Well # 4
County Lane
Well Total Depth 4335 140,89 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor A.L. Abercrombie, Inc. License Number 5393
Address Rt. 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 2 Month: 12 Year: 19 94

Plugging proposal received from Mr. Dipman
(company name) A.L. Abercrombie, Inc. (phone) 316-793-8186

were: 4 1/2" at 2176' w/650 sx cement, PBD 1928', Perfs at 1898-1948'
1st plug fill 4 1/2" casing with 300 lbs. hulls and 175 sx cement.
2nd plug check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:10 a.m. Day: 2 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug filled 4 1/2" casing with 200 lbs. hulls and 125 sx cement.
Pumping pressure 0-700 psi and shut in 500 psi.

2nd plug pressured 8 5/8" X 4 1/2" annulus to 1500# and pumped 1/4 bbl. cement

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

(if ~~XXXXXX~~ observe this plugging.

INVOICED

Signed Richard Lacey
(TECHNICIAN)

DATE 12-12-94
INV. NO. 41885

RECEIVED
KANSAS CORPORATION COMMISSION
12-8-94
DEC 08 1994
CONSERVATION DIVISION
WICHITA, KS