

9-11

To: 1 061134
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,481-0000

SW NW SE, SEC. 6, T 17 S, R 29 W/EX

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914

Lease Name G.R. Dodge Trust Well # 1

Operator: H & C Oil Operating Inc.

County Lane 151.13

Name & Address P.O. Box 86

Well Total Depth 4650 feet

Plainville, KS 67663

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R & C Drilling Company License Number 9087

Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 7:30 a.m. Day: 11 Month: 9 Year: 19 88

Plugging proposal received from John Weis

(company name) R & C Drilling Company (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2232-60'

1st plug at 2260' with 50 sx cement, 2nd plug at 1330' with 80 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 11 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement

2nd plug at 1330' with 80 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXXX) observe this plugging.

DATE 9-22-88

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 22365