

1080240

TO:
STATE CORPORATION COMMISSION

API NUMBER 15-101-21,014-6001
NW NE NW SEC. 3, T 6 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3540 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SHAY WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 147.94

OPERATOR LICENSE # 4629

WELL TOTAL DEPTH 4552 FEET

OPERATOR: BRITO OIL COMPANY, INC PRODUCTION CSG: SIZE 4 1/2" @ 4552' WITH 250 SX

NAME AND 120 S MARKET, SUITE 400 SURFACE CASING: SIZE 8 5/8" @ 387' WITH 225 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-25,343 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31, RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 19 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BUD BRUNGARDT

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: PERFS AT 4520-32,4459-77, CIBP @ 2050. PERFS @ 1930-2000
STAGE COLLAR @ 2214 WITH 525 SX CEMENT.

ALLIED PUMPED 400# HULLS, 80 SX CEMENT DOWN 4 1/2" CASING. MAXIMUM PSI @ 1300#. SHUT IN AT
800#. PUMPED DOWN 8 5/8 X 4 1/2 ANNULAS 20 SX CEMENT. SHUT IN AT 200#.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 19 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

ALLIED PUMPED DOWN 400# HULLS, 80 SX CEMENT DOWN 4 1/2" CASING. MAXIMUM PSI @ 1300#. SHUT IN
AT 800#. PUMPED DOWN 8 5/8 X 4 1/2 ANNULAS 20 SX CEMENT. SHUT IN AT 200#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Kenneth P. Stult
(TECHNICIAN)

FORM CP-2/3

DATE 3-1-99

INV. NO. 60666