

1 060235

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,980-0000

SW SE NE, SEC. 6; T 17 S, R 29 W

2310 feet from ~~N~~ section line

990 feet from ~~E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114

Lease Name Direen Well # 1

Operator: National Development Company

County Lane

Name & Address 205 East Central, Suite 120

Well Total Depth 4590 149.18 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address P. O. Box 823, Great Bend, KS 67530

Company to plug at: Hour: 5:00 am Day: 23 Month: May Year: 19 84

Plugging proposal received from Bill Draney

(company name) Duke Drilling (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2210' with 50 sx cement

2nd plug at 1400' with 50 sx cement

3rd plug at 470' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 am Day: 23 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2210' with 50 sx cement, 2nd plug at 1400'

with 50 sx cement, 3rd plug at 470' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat

hole with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

If additional description is necessary, use BACK of this for Wichita, Kansas

INVOICED

DATE 5-29-84

INV. NO. 1686

5.73

Signed Paul A. Luthi (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAY 25 1984 5-25-84 CONSERVATION DIVISION