

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,936-0000

SW SE NE, Sec. 6, T 17 S, R 29 W/X

2310 feet from N/X section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5040

Lease Name Dirreen Well # 1

Operator: Alpine Drilling Co., Inc.
Name & 200 East First, Suite 500
Address Wichita, KS 67202

County Lane

Well Total Depth 4610 feet 149.82

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor J.W. Drilling Co., Inc. License Number 5137

Address 200 East First, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 24 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Walt Coldwater

(company name) J.W. Drilling (phone) 316-263-5705

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2190' with 50 sx cement

2nd plug at 1680' with 50 sx cement

3rd plug at 480' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Signed Steve Quimont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 am Day: 25 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2190' with 50 sx cement, 2nd plug at 1680' with

50 sx cement, 3rd plug at 480' with 40 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement, plug water well with 5 sx cement (Resor will plug water

well)

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing

Bob Tarbutton gave the orders

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1984
2-29-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~xxx~~ / did not) observe this plugging.

Signed Steve Quimont
(TECHNICIAN)

INVOICED
DATE 2-5-84
INV. NO. 0512