

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,910-0000

NE SE NE, Sec. 6, T 17 S, R 29 W/E

1660 feet from N/E section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Dirreen "G" Well # 1

Operator: Donald C. Slawson
Name & 200 Douglas Building
Address Wichita, KS 67202

County Lane

Well Total Depth 4600 feet 149.50

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 470

316-263-3201

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 4:00am Day: 22 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Ron Rowe

(company name) Slawson (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2220' with 50 sx cement

2nd plug at 1360' with 60 sx cement

3rd plug at 520' with 50 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Signed *Don C. Slawson*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 22 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1360' with

60 sx cement, 3rd plug at 520' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Halliburton

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed *Don C. Slawson*
(TECHNICIAN)

INVOICED

DATE 2-1-84

INV. NO. 92356

1-22

RECEIVED STATE CORPORATION COMMISSION

JAN 26 1984

CONSERVATION DIVISION Wichita, Kansas