



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 1 1963
 7-1-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Quattlebaum of National Drilling Co. Inc. has this date requested permission to plug the following described well:

Mr. Quattlebaum guarantees payment of the plugging fee.

Operator's full Name: Underwriters Oil Corporation.

Complete Address: 300 Weber Bldg., Lake Charles, Louisiana.

Lease Name: Chance Well No. 1

Location: NE-NW-MW Sec. 30 Twp. 18 Rge. (E) (W) 31

County Scott Total Depth 4015 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Quattlebaum was instructed to plug the well as follows:

- 255' -- 8 5/8" Surface pipe, cement circulated.
- Circulate hole with heavy mud, set plug @ 540' and 20 Sx cement.
- " " 250' with 1/4 sk hulls & 20 Sx cement.
- " " 40' with 1/2 sk hulls & 10 Sx cement.

Very truly yours,

H. L. Nichols
 Conservation Division Agent