

State of Kansas



15-17-2067-000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1974
11-18-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahr of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Lahr guarantees payment of the plugging fee.

Operator's full Name: Marsh Oil Associates, Davies & Fitzgerald,

Complete Address: 1303 Philtower, Tulsa, Oklahoma.

Lease Name: B J. Pfenninger Well No. 1

Location: 1320' FNL & 1320' FNL-NE/4 Sec. 33 Twp. 18 Rge. (E)(W)31

County: Scott Total Depth 2840' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Lahr was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 150 Sx.

Circulate hole with heavy mud. Pull DP to 850' and displace 50 Sx. cement thru DP. Pull DP to 550' and displace 35 Sx. cement thru DP. Pull DP, set bridge 45' with 1/2 sack hulls and 15 Sx. cement to base of cellar.

Very truly yours,

W. L. Pfenninger
Conservation Division Agent