



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company,

Complete Address: Box #2585, Amarillo, Texas.

Lease Name: Blume Well No. 1

Location: CSE-SE Sec. 33 Twp. 18 Rge. (E)(W) 31

County: Scott Total Depth 2856 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

288'--8 5/8" Surface casing, cement circulated with 230 Sx.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.

cement thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 8-12-68

Very truly yours,

Conservation Division Agent