



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 13, 1964

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co as this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company

Complete Address: P.O. Box 3108, Wichita, Kansas

Lease Name: Reese Well No. 3

Location: NE NW SE Sec. 30 Twp. 16 Rge. 1 CEX (W) X

County Saline Total Depth 2671' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2655' and cement with 5 sacks.

Fill hole with mud to 155'. Set rock bridge from 155'

to 145' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

Conservation Division Agent