



15-169-00543-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

April 22, 1966

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 - 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Vernon Faulconer

Complete Address: 336 Union Center Bldg., Wichita, Kansas

Lease Name: Reese Well No. 2

Location: SW NE SE Sec. 30 Twp. 16 Rge. 1 (K)(W) X

County Saline Total Depth 2679' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 2660' and cement with 6 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

*Alfred J. Loman*  
Conservation Division Agent