

6-24-88 341

To: 1 120107
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,770-0000
SW NW NW, SEC. 8, T 17 S, R 29 W/E
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address: 104 South Broadway
Wichita, KS 67202

Lease Name Sharp "C" Well # 1
County Lane 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 470

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. Well Service License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 1 p.m. Day: 24 Month: 6 Year: 19 88

Plugging proposal received from Clint Base

(company name) Plains Inc. Well Service (phone) 913-798-3995

were: 4 1/2" at 4639' PBD 4587' Perfs at 4187-4535 (6 sets) Elevation 2824'GL.

1st plug set wooden plug w/wire wickers-pushed to 4130', put 50 ft sand on top of plug, put 4 sx cement on top of sand-approved by Dennis Anderson.

2nd plug pump 50 sx cement, 200 lbs. hulls, and 90 sx cement.

3rd plug pump 75 sx lite cement down annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 24 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pushed plug to 4130' and sanded back to 4130' with 4 sx cement on top of sand with dump bailer,

2nd plug pumped in 4 1/2" casing with 50 sx cement, 200 lbs. hulls, 85 sx cement.

Pumping pressure 0-1300 psi and shut in 1300 psi. Used 60/40 Pozmix 6% gel by Allied.

3rd plug pumped in 8 5/8" X 4 1/2" annulus with 5 sx 60/40 Pozmix 6% gel cement and 75 sx ATL cement. Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel and ATL cement by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / x440-062) observe this plugging.

DATE 7-19-88

Signed Duane Rankin (TECHNICIAN)

INV. NO. 21440