

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21316-00-00  
Spot: NESENE Sec/Twnshp/Rge: 7-17S-29W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: YORK B H Well Number: 1  
County: LANE Total Vertical Depth: 4930 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4629 WITH 250 SX CMT  
Surface Casing Size: 8.625 feet: 385 WITH 240 SX CMT

\$160<sup>23</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2003 12:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: \_\_\_\_\_ Phone: (316) 727-3410

Proposed Plugging Method: SAND BACK TO 4380' & 4 SX CMT ON TOP OR PUMP 25 SX CMT & 400# HULS. GEL SPACER TO 1200'. CMT OT SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/07/2003 1:40 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:  
PERFS AT 4437-92 & 4518-20'. DV TOOL @ 2222' WITH 420 SX CMT. 1ST PLUG PUMPED 300# HULLS- 30 SX CMT - 15 SX GEL - 195 SX CMT. CASING WENT ON VACUUM. 2ND PLUG PUMP 1 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. PRESSURED TO 500#. 8/11/03: TOC @ 1600'. 10/02/03: FILLED CASING BACK TO SURFACE WITH 90 SX CMT. WITNESSED BY MICHAEL MAIER.

RECEIVED  
10-07-2003  
OCT 07 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
OCT - 3 2003  
KCC Dodge City

Signed Steve Durrant

(TECHNICIAN)  
INVOICED  
10-7-03  
2004060585