

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20577-00-00
Spot: CNENESW Sec/Twnshp/Rge: 7-17S-29W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: YORK V Well Number: 1
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/150.15
Surface Casing: Size 8.625 feet: 451 WITH 350 SX CMT
Production: Size 4.5 feet: 4619 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/20/2001 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND TO 4192' & 4 SX CMT. 1ST PLUG AT 1200' WITH 80 SX CMT. 2ND PLUG AT 490' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/20/2001 11:15 AM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4580'. PERFS AT 4488, 4451, 4431-39, 4244-47'. SANDED TO 4192' & 4 SX CMT. 1ST PLUG AT 1200' WITH 80 SX CMT. 2ND PLUG AT 490' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1225' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael J Maier
(TECHNICIAN)

RECEIVED
10-04-2001
OCT 04 2001

INVOICED SEP 24 2001

DATE 10-4-01

INV. NO. 2002060729

KCC WICHITA

Form CP-2/3