

1 070530

292(107) R

API NUMBER 15-101-21,373-6000
NW NE SE, SEC. 10, T 17 S, R 29 W/E
2310 feet from S section line
990 feet from E section line

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
Operator License # 5420
Operator: White & Ellis Drilling, Inc.
Name & Address 401 East Douglas, Suite 500
Wichita, KS 67202

Lease Name Snider "A" Well # 1
County Lane 149.34
Well Total Depth 4595 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated
Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 7:30 p.m. Day: 30 Month: 4 Year: 19 87

Plugging proposal received from Bob Casper
(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2795' est.
Anhydrite 2209-30'

1st plug at 2220' with 50 sx cement, 2nd plug at 1380' with 80 sx cement,
3rd plug at 400' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

 Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 10:15 p. Day: 30 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,
2nd plug at 1600' with 80 sx cement,
3rd plug at 400' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE OF KANSAS
05-06-1987
MAY 6 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-87
INV. NO. 16814

Signed Dan Gooden
(TECHNICIAN)