

1 050491

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,148 0000  
200' East of  
NE SW SW , SEC. 10 , T 17 S, R 29 W/E

990 feet from S section line  
4090 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name D.J. Well # 1-10

Operator: Gear Petroleum Co., Inc.

County            Lane 152.10

Name & Address 300 Sutton Place

Well Total Depth 4680 feet

Wichita, KS 67202

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 321 ✓

Abandoned Oil Well            Gas Well            Input Well            SWD Well            O&A X

Other well as hereinafter indicated           

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 3 Month: April Year: 19 85

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1110' with 50 sx cement

3rd plug at 600' with 40 sx cement

4th plug at 360' with 40 sx cement

Solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey  
cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement.  
Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 10:00 am Day: 3 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1110' with  
50 sx cement, 3rd plug at 600' with 40 sx cement, 4th plug at 360' with 40 sx cement,

5th plug & 6th plug - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 7th plug to circulate rat hole with 15 sx cement.

APR 12 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

04-12-1985

INVOICED

(xxx did not) observe this plugging.

DATE 4-16-85

Signed Richard W. Lacey (TECHNICIAN) 

INV. NO. 2247