

To: **1 080009**
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,122-0001

SE NW SW, SEC. 10, T 17 S, R 29 **WEX**

1650 feet from S section line

4290 feet from E section line

12-27

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420

Lease Name Snider Well # 1

Operator: White & Ellis Drilling

County Lane 150.51

Name
Address P.O. Box 48848

Well Total Depth 4631 feet

Wichita, KS 67201-8848

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Inc. License Number

Address

Company to plug at: Hour: 1 p.m. Day: 27 Month: 12 Year: 1995

Plugging proposal received from Charles Schmidt

(company name) White & Ellis Drilling (phone) 5420

were: 4 1/2" at 4630' w/700 sx cement, PBD 4550', Perfs at 4124-26, 4170-76, 4136-40, 4258-62,

4329-34, 4489-92'

1st plug pump 2 sx hulls and 25 sx cement, gel spacer to 2206',

2nd plug cement to surface.

Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3 p.m. Day: 27 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT

1st plug pumped down 4 1/2" with 25 sx cement, 200 lbs. hulls, 12 sx gel, and 165 sx cement.

Well on vacuum. 4 1/2" X 8 5/8" annulus-pumped 2 barrels, 300 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE JAN 12 1996

INV. NO. 44563

Signed Kevin D. Shute
(TECHNICIAN)