

To: 1 031419  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 31283  
Operator: Rheem Resources, Inc.  
Name: 100 S. Main, Ste. 505  
Address: Wichita, KS 67202

API NUMBER 15- 101-21,732-0000  
NE SW, SEC. 9, T 17 S, R 29 W/2  
1980 feet from S section line  
1980 feet from W E section line  
Lease Name Snider Well # 1  
County Lane 149.82  
Well Total Depth 4610 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 12 Month: 11 Year: 19 96

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2215-38'

1st plug at 2220' with 50 sx cement, 2nd plug at 1230' with 80 sx cement,

3rd plug at 690' with 40 sx cement, 4th plug at 330' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1 p.m. Day: 12 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,

2nd plug at 1230' with 80 sx cement,

3rd plug at 690' with 40 sx cement,

4th plug at 330' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# flowseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE NOV 14 1996

WFL NO. 46969

Signed Steve Durrant  
(TECHNICIAN)