

1 070459

11-7-87

API NUMBER 15- 101-21,427-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C E/2 E/2 SE, SEC. 9, T 17 S, R 29 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1320 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421

Lease Name Snider Well # 1

Operator: Boger Brothers Drilling Inc.

County Lane 151.13

Name & Address P.O. Box 723

Well Total Depth 4650 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling Inc. License Number 9421

Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 5 p.m. Day: 7 Month: 11 Year: 19 87

Plugging proposal received from Rick Smith

(company name) Boger Brothers Drilling Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2807' Anhydrite 2207-2220'

1st plug at 2220' with 50 sx cement, 2nd plug at 1380' with 80 sx cement,

3rd plug at 260' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 p.m. Day: 7 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,

2nd plug at 1380' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE NOV 20 1987

Signed Dan Hodson (TECHNICIAN)

INV. NO. 18900