

1 070047

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101 - 21,235.0000 ^R

S/2, NW/4 SEC. 9, T 17 S, R 29 (W/E)
4300 feet from S section line
2010 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Snider "U" Well # 1

Operator: Donald C. Slawson
Name & Address: 200 Douglas Bldg.
Wichita, Ks. 67202

County Lane 150.09
Well Total Depth 4618 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drlg. Co. License Number 5657

Address Wichita, Ks.

Company to plug at: Hour: 5:00 AM Day: 7 Month: 11 Year: 19 85

Plugging proposal received from Bill Horigan

(company name) Donald C. Slawson (phone) 316-263-3201

work: To fill hole with heavy mud and spot cem. through drill pipe. Elevation - 2822, Anhydrite 2220

1st plug at the base of Anhydrite with 50 sx. cem. 2nd plug at base of Cheyenne with 50 sx. cem. 3rd plug 30' below surface pipe with 50 sx. cem. 4th plug at 40' with wiper plug and cem. to surface, 5th plug circulate rat hole with 15 sx. cem.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:40 AM Day: 7 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx. cem. 2nd plug at 1380' with 50 sx. cem. 3rd plug at 390' with 50 sx. cem.

4th plug at 40' with wiper plug and cem. to surface with 10 SX. 5th plug circulate rat hole with 15 sx. cem.

Remarks: 60/40 per. 6% gel Halliburton cementers
(if additional description is necessary, use BACK of this form.)

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 12-9-85 INV. NO. 11323

NOV 18 1985 11-18-85 CONSERVATION DIVISION Wichita, Kansas

Signed Dan Goodrow (TECHNICIAN)