

1 070148

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION S/2 SE SW, SEC. 9, T 17 S, R 29 W/E
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- 101-21,234 -0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Operator: Donald C. Slawson

Name &

Address 200 Douglas Building

Wichita, KS 67202

660 feet from S section line

3300 feet from E section line

Lease Name Snider S Well # 1

County Lane 150.48

Well Total Depth 4630 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 12 Month: March Year: 19 86

Plugging proposal received from Billy Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4629' PBTD 4569' Perfs at 4533-4541.5'

1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 12:30 pm Day: 12 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of
 sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel 70 sx cement, 10 sx
 gel, 1 sack hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 300 psi,

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2500' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13036

3-12

observe this plugging.
STATE CORPORATION COMMISSION

MAR 20 1986
 3-20-86
 CONSERVATION DIVISION
 Wichita, Kansas

Signed Dan Goodrow
(TECHNICIAN)FORM CP-2/3
Rev. 01-84