

MAR 1 2 1987

To: 1 070512
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,366-0000
SW NW SE, SEC. 15, T 17 S, R 29 W/10
1770 feet from S section line
2110 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6194

Lease Name Riley Well # 1

Operator: ESP Development, Inc.
Name & Address RR #1, Box 18
Paradise, KS 67658

County Lane 149.39
Well Total Depth 4615 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 12 Month: 3 Year: 19 87

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 913-625-7966

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2799'
Anhydrite 2187-2222'

1st plug at 2220' with 50 sx cement, 2nd plug at 1475' with 80 sx cement,

3rd plug at 400' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

 Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 p.m. Day: 12 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,

2nd plug at 1475' with 80 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. STATE CORPORATION COMMISSION
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-20-87

INV. NO. 16349
3-12

Signed Dan Goodrow MAR 18 1987
(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas