

1 070157

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,301-0000  
S/2. NW NE, SEC. 15, T 17 S, R 29  
4190 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Snider Well # 4-15

Operator: Gear Petroleum Co., Inc.

County Lane 151.13

Name & Address 300 Sutton Place

Well Total Depth 4650 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 3:50 am Day: 26 Month: March Year: 19 86

Plugging proposal received from Bruce Fickle

(company name) Red Tiger (phone) 316-263-1201

Elevation 2805 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2195-2225'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 1300' with 80 sx cement

3rd plug at 360' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:30 am Day: 26 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2225' with 50 sx cement, 2nd plug at 1300' with 80 sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 30' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE APR 1 1986

STATE CORPORATION COMMISSION

Signed Dan Goodson (TECHNICIAN)

INV. NO. 13206

MAR 31 1986 03-31-1986 CONSERVATION DIVISION