

1 060540

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,145-6000  
SE SE NW, SEC. 15, T17 S, R29 W2E

2970 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6889

Lease Name Eaton Well # 15-6-4

Operator: Oxford Exploration Company

County Lane 150.80

Name & Address 1550 Denver Club Building

Well Total Depth 4640 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335 ✓

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 11 Month: April Year: 1985

Plugging proposal received from Lloyd Dellett

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2160' with 50 sx cement

2nd plug at 1820' with 50 sx cement

3rd plug at 370' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 pm Day: 11 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement, 2nd plug at 1820' with 50  
sx cement, 3rd plug at 370' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
04-23-1985  
APR 23 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
Conservation Division  
Wichita, Kansas  
if additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE 5-3-85

Signed Paul A. Luthi  
(TECHNICIAN)

INV NO 7936  
4-11-85