

1030354

API NUMBER 15-101-21,089-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 S/2 NE, SEC. 15, T 17 S, R 29 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3630 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Fred Well # 1-15

Operator: Gear Petroleum Co., Inc.
Name & Address 300 Sutton Place
Wichita, KS 67202

County Lane Lane 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 341 ✓

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 31 Month: December Year: 19 84

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2220' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

01-09-1985
JAN 09 1985

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 pm Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 840' with 50

sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-15-85

INV. NO. 6434

Signed Steve Durrant (TECHNICIAN)