

4-13

To: 1 070658
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,509-00050
SW NW NW, SEC. 14, T 17 S, R 29 W/EX
4456 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4661 Lease Name Fred Well # 1-14
Operator: Galloway Petroleum Exploration, Inc. County Lane 148.85
Name & Address 360 Broadway Plaza Building
Wichita, KS 67202
Well Total Depth 4580 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783
Address 340 Broadway Plaza Building, 105 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 13 Month: 4 Year: 19 89

Plugging proposal received from Carl McGuire
(company name) Galloway Drilling Company, Inc. (phone) 316-263-1793
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2773'
Anhydrite 2166-98'

1st plug at 2200' with 50 sx cement, 2nd plug at 1650' with 80 sx cement,
3rd plug at 360' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 2:15 p.m. Day: 13 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,
2nd plug at 1650' with 80 sx cement,
3rd plug at 360' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
04-19-1989
APR 19 1989

CONSERVATION DIVISION
WICHITA, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED (DUPLICATE) observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 4-24-89
INV. NO. 24468 JUL 11 1989
4-13