

1 030523

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,217-6000

TECHNICIAN'S PLUGGING REPORT

SEC. 13, T 17 S, R 29 W/E
2970 feet from S section line
3630 feet from E section line

Operator License # 5161

Lease Name Sutton "V" Well # 1

Operator: Palomino Petroleum

County Lane 150.15

Name &

Address P. O. Box 18610

Well Total Depth 4620 Mississippi feet

Wichita, KS 67218

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 7:00 am Day: 17 Month: September Year: 19 85

Plugging proposal received from John Taylor

(company name) DNB (phone) 316-687-5471

Elevation 2772 KB

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2156-2184

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 50 sx cement

3rd plug 30' below the surface pipe with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:50 pm Day: 17 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2185' with 50 sx cement, 2nd plug at 1250' with 80 sx

cement, 3rd plug at 295' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx

cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Signed Steve DuPont (TECHNICIAN)

DATE SEP 24 1985

INV. NO. 10243