

To: **1090560**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-16

API NUMBER 15-101-20,889-0000

SE NE NE, SEC. 13, T 17 S, R 29 W/E
4290 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31142

Lease Name Hazel Eaton Well # 2-13

Operator: Petroleum Property Services, Inc.
Name & Address 155 N. Market, Ste. 1010
Wichita, KS 67202

County Lane

Well Total Depth 4620 150.15 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 11:20 a.m. Day: 16 Month: 6 Year: 1995

Plugging proposal received from Bill Hammack

(company name) Petroleum Property Services, Inc. (phone) 316-265-3351

were: 4 1/2" at 4598' w/175 sx cement, PBTD 4598', Perfs at 4379-83, 4395-98, 4408-12, 4421-27'
Perforated at 1350' with 250 sx cement to surface
1st plug pump 4 sx hulls and cement to 0'.

 Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 16 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 4 sx hulls and 264 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Pressured backside to 300 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 6-30-95

INV. NO. 43023