

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,914-0000

SE/4, Sec. 12, T 17 S, R 29 W

330 feet from ~~X~~/S section line

990 feet from ~~X~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name EATON "U" Well # 1

Operator: CHIEF DRILLING Co., INC.
Name & Address 905 CENTURY PLAZA
WICHITA, KS 67202

County LANE

Well Total Depth 4630 feet 150.47

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor WARRIOR DRILLING Co. License Number 5883

Address 905 CENTURY PLAZA, WICHITA, KS 67202

Company to plug at: Hour: 5 PM Day: 17 Month: JAN Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO MARION BURRIS

(company name) WARRIOR (phone) _____

were: to use 60/40 Pozmix, w/2% gel - 3% CC. AND SPOT THE
1ST plug @ 2180' w/50 dy - 2ND plug @ 1710 w/50 dy
3RD plug @ 1080' w/50 dy - 4TH plug @ 390 w/40 dy
5TH plug @ 40' w/ solid bridge of 1/2 subiron mud @ 40'
wiper plug and 10 dy to surface. Circ. rat hole w/15 dy
& mouse hole w/10 dy.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7 PM Day: 17 Month: Jan Year: 1984

ACTUAL PLUGGING REPORT All plugs ordered above were
set through drill pipe and spaced
with heavy mud. Cementing by Allied,
ticket # 28611.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~was~~ / did not) observe this plugging.

INVOICED

DATE 1-26-84 RECEIVED
STATE CORPORATION COMMISSION
INV. NO. 9249-W 01-23-1984
JAN 23 1984

Signed R. Barluttan
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82