

1080232

TO: STATE CORPORATION COMMISSION

12-3

API NUMBER 15-101-20,186-6850
C NE SW SEC. 12, T 17 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME EATON WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY LANE 148.53

OPERATOR LICENSE # 31627

WELL TOTAL DEPTH 4570 FEET

OPERATOR: WHITETAIL CRUDE, INC

PRODUCTION CSG: SIZE 5 1/2" @ 4563' WITH 200 SX

NAME AND PO BOX 544

SURFACE CASING: SIZE 8 5/8" @ 343' WITH 150 SX

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR FRITZLER TRUCKING, INC LICENSE NUMBER NA

ADDRESS PO BOX 544, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 03 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) FRITZLER TRUCKING, INC (PHONE) 785-798-3641

WERE: PERFS AT 4548-53, 4519-24, (CIBP @ 4275), (4204-12 SQUEEZED PERFS 150 SX), 4211-13
1ST PLUG SANDED BACK TO 4100' WITH 5 SX CEMENT ON TOP. 2ND PLUG PERFORATE AT 1200'. ALLIED
PUMPED DOWN 5 1/2 60 SX CEMENT LAST 20 SX CEMENT HAD 50# HULLS MIXED IN. MAXIMUM PSI PRESSURE
AT 700#. SHUT IN AT 500#. 3RD PLUG SHOT CASING AT 644' PULLED UP TO 600' PUMPED 40 SX
CEMENT, 4TH PLUG PULLED UP TO 40' PUMPED 10 SX CEMENT. CEMENT STAYED AT SURFACE.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 03 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 4100' WITH 5 SX CEMENT ON TOP. 2ND PLUG LOG-TECH PERFORATED AT
1200'. ALLIED PUMPED DOWN 5 1/2 60 SX CEMENT LAST 20 SX CEMENT HAD 50# HULLS MIXED IN.
MAXIMUM PSI PRESSURE AT 700#. SHUT IN AT 500#. 3RD PLUG SHOT CASING AT 644' PULLED UP TO
600' PUMPED 40 SX CEMENT, 4TH PLUG PULLED UP TO 40' PUMPED 10 SX CEMENT. CEMENT STAYED AT
SURFACE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 644' OF 5 1/2' CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3

RAWZ

DEC 16 1998

60450