

To: 1 030839
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21.405-0000
100' N of S/2
S/2 SE, SEC. 11, T 17 S, R 29 W/8

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

430 feet from S section line

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 North Market, Suite 205
Wichita, KS 67202

1320 feet from E section line

Lease Name James Well # 1-E

County Lane 150.48

Well Total Depth 4630 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 15 Month: 8 Year: 19 87

Plugging proposal received from Gary Christopher

(company name) Pickrell Drilling Company (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2791' GL
Anhydrite 2190-2218'

1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 350' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 p.m. Day: 15 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 397' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement. 08-19-1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

(if additional description is necessary, use BACK of this form.)

DATE 8-21-87

Signed Steve Stewart
(TECHNICIAN)

INV. NO. 17912