

1 060384

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,069 - 0000

S/2 NW NW, SEC. 11; T 17 S, R 29 W/E

4290 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Peters 'J' Well # 1

Operator: Donald C. Slawson
Name & Address: 200 Douglas Building
Wichita, KS 67202

County Lane

Well Total Depth 4640 150.80 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated 11-05-1984

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 30 Month: October Year: 19 84

Plugging proposal received from Jim Loftis

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1250' with 50 sx cement

3rd plug at 420' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 am Day: 30 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1250' with 50
sx cement, 3rd plug at 420' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3%cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED (Do not) observe this plugging.

DATE 11-7-84

INV. NO. 4664

10-30

Signed Paul A. Luthie SQ
(TECHNICIAN)