

To: 1 030671
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 SE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,291 .0000
SE NE, SEC. 15, T 17 S, R 29 (W/E)
3630 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9427
Operator: Sharp Engineering
Name & Address: 708 One Main Place
Wichita, KS 67202

Lease Name F. Eaton Well # 1
County Lane 149.50
Well Total Depth 4600 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling License Number 5302
Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 9 Month: March Year: 19 86

Plugging proposal received from Bruce Fickle
(company name) Red Tiger (phone) 316-263-1201
Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2201 base
1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 7:15 am Day: 9 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1300' with 80
sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

STATE CORPORATION COMMISSION

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
MAR 12 1986
DATE
NO. 12961 3-9

MAR 11 1986
03-11-1986
CONSERVATION DIVISION
Wichita, Kansas