

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21389-00-00
Spot: CN2N2NE Sec/Twnshp/Rge: 14-17S-29W
4950 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: EATON A Well Number: 1-14
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet: \$149.50
Surface Casing: Size 8.625 feet: 275 WITH 160 SX CMT
Production: Size 4.5 feet: 4599 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/28/2001 9:40 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ROGER Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SAND TO 4370' & 4 SX CMT. 1ST PLUG AT 1200' WITH 80 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 30' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/28/2001 10:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4589'. PERFS AT 4542-46, 4536-38, 4509-12, 4492-94, 4419-22'. CEDAR HILLS LEAK IN CASING AT 1650'. SANDED TO 3990' WITH 4 SX CMT. HOOKED ONTO CASING AND PUMPED 400# HULLS & 150 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN 50#. COULD ONLY PULL 1/2" STRETCH. PRESSURED BACKSIDE TO 1000#. COULD NOT PUMP INTO. CHECKED TOC ON 12/31/2001. TOC @ 400'. SWIFT SERVICES PUMPED 25 SX CMT TO FILL CASING.

Remarks: USED 60/40 POZMIX 6% GLE BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION
01-08-2002
JAN 08 2002
CONSERVATION DIVISION

Signed Michael Maier
(TECHNICIAN)

INVOICED JAN 04 2002
DATE Jan 9-02
INV. NO. 2002061220

POST-CP-2/3