

To: 1 070397
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-26-87
API NUMBER 15- 101-21,408 -00-00
W/2 W/2 NW, SEC. 19, T 19 S, R 27 W/EX
3960 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address: 200 Douglas Building
Wichita, KS 67202

Lease Name United Methodist B Well # 1
County Lane 151.61
Well Total Depth 4665 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Company Inc. License Number 5657
Address 200 Douglas Bldg., 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 26 Month: 8 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company Inc. (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2737'
Anhydrite 2057-83'

1st plug at 2070' with 50 sx cement, 2nd plug at 1290' with 80 sx cement,
3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 26 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,
2nd plug at 1290' with 80 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

8-31-87

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
If called / observe this plugging.

Signed Dan Godwin (TECHNICIAN)

DATE 9-3-87

INV. NO. 18019

8-26