

To: 1 041221  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-21,731-0000

NW SW SW, SEC. 32, T 19 S, R 27 W XX

990 feet from N&S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name West-32C Well # I

Operator: Ritchie Exploration, Inc.  
Name & Address 125 N. Market, Ste. 1000  
Wichita, KS 67202

County Lane 149,50

Well Total Depth 4600 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Ste. 500, Wichita, KS 67201-8848

Company to plug at: Hour: 3:50 a.m. Day: 27 Month: 11 Year: 19 96

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1985-2022'

1st plug at 2022' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 50 sx cement, 4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:45 a.m. Day: 27 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2022' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# flowseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

1. (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE DEC 03 1996

INV. NO. 47090

Signed Stephen J. Pfeifer (TECHNICIAN)