

1 050225

15-171-30065-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 7-2-66
C NE NE SW, SEC. 26, T 18 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6814

Lease Name Steinberg Well # 1-26

Operator: Cargill, Inc.
Name & Address Suite 604, One Main Place
Wichita, KS 67202

County Scott

Well Total Depth 2800 91.00 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:00 pm Day: 17 Month: May Year: 1984

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2348

were: 4 1/2 set at 2799' Top perf 2748

1st plug sand back to 2700' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and pump an additional 225 sx cement.

Plugging Proposal Received by Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:00 pm Day: 17 Month: May Year: 1984

ACTUAL PLUGGING REPORT 4 1/2" set at 2799' Top Perf 2748'

1st plug sanded back to 2700' and dumped 4 sx cement on top of sand, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pump an additional 225 sx cement.

Maximum pressure 500# and shut-in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 993' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-25-84

INV. NO. 1651

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1984
5-23-84
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacy
(TECHNICIAN)