

To: 1 050933
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-12-87
API NUMBER 15- 171-20,043-0000
C NW, SEC. 33, T 18 S, R 31 W/E
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4311

Lease Name W.B. Wise Well # 1

Operator: Methanol Production Corporation
Name & Address 165 South Union, Suite 500
Lakewood, CO 80228

County Scott 91.52

Well Total Depth 2816 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box E, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 12 Month: 10 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 2813' PBTD 2796' Perfs at 2779-87'

1st plug pump 1 sx hulls and 20 sx cement to 2700',

2nd plug perforate at 1450' and pump 50 sx ATL cement down 5 1/2",

3rd plug pump 100 sx ATL down 8 5/8".

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 12 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 2600'

2nd plug pumped 50 sx cement at 1400',

3rd plug pumped 40 sx cement at 400',

4th plug pumped 10 sx cement at 40'.

STATE CORPORATION COMMISSION

OCT 16 1987

10-16-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest. Recovered 2039' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 10-00-87

INV. NO. 18576

10-12