

225
P

3-27

051144

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,125-0000
C SW/4, SEC. 33, T 18 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

1320 feet from S section line
3960 feet from E section line

Operator License # 3857

Lease Name Rueter Well # 1-33

Operator: Unico Inc.
Name & Address: 165 South Union Blvd., Suite 602
Lakewood, CO 80228

County Scott 94.90

Well Total Depth 2920 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 27 Month: 3 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 4 1/2" at 2919' PBSD 2908' Perfs at 2890-2903, 2760-72'

1st plug pump 2 sx hulls and 20 sx cement,

2nd plug pump 80 sx cement at 1400', 3rd plug pump 40 sx cement at 370',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by James R, Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 27 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement,

2nd plug pumped 80 sx cement at 1400',

3rd plug pumped 40 sx cement at 370',

4th plug pumped 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1989
3-29-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1420' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICE
I (did / did not) observe this plugging.
DATE 4-20-89

Signed Richard W. Lacy
(TECHNICIAN)

INV. NO. 24406

3-27